DETROIT MECHANICAL LUBRICATOR

WHEN DETROIT MECHANICAL LUBRICATOR IS APPLIED THE QUESTIONNAIRE FURNISHED BY THE MANUFACTURER MUST BE FILLED OUT AND SENT WITH THE ORDER.

DETROIT MECHANICAL LUBRICATORS SHALL BE HEATED WITH SATURATED STEAM, FOR BOTH MANUAL HEAT CONTROL AND THERMOSTATIC CONTROL.

THE STOP VALVE MAY BE LOCATED IN THE STEAM VALVE STAND OR OTHER CONVENIENT SOURCE OF SUPPLY OF SATURATED STEAM.

DETROIT MECHANICAL HIGH PRESSURE TERMINAL CHECKS TO BE APPLIED DIRECTLY TO THE STEAM PIPES AND CYLINDER BARRELS UNLESS OTHERWISE SPECIFIED.

THE PIPE LEADING FROM THE AIR PUMP EXHAUST PIPE FOR THE PURPOSE OF HEATING THE LUBRICATOR, TO BE A 1" IRON PIPE, WHICH WILL BE REDUCED TO COPPER TUBING, $\frac{1}{4}$" IRON PIPE SIZE, AT A POINT CLOSE TO THE LUBRICATOR.

THE JAWS AND ENDS FURNISHED BY MANUFACTURER FOR CONNECTING ROD AND DRIVE ARM ARE TO BE BRAZED ON THE ROD AND ARM INSTEAD OF WELDED.

VICTORIA A MINAS (BRASIL) (BRAZIL)

ALL ENGINES BUILT FOR THIS ROAD MUST BE EQUIPPED WITH DETROIT LUBRICATORS.

HENNESSY LUBRICATORS

ALL ORDERS TO HENNESSY LUBRICATOR COMPANY FOR HENNESSY LUBRICATORS TO INCLUDE THE FOLLOWING GUARANTEE CLAUSE;-

"ANY EXTRA CHARGES INCURRED AT BUILDER'S PLANT INSTALLING THESE LUBRICATORS, ATTRIBUTABLE TO YOUR LUBRICATOR ARE TO BE FOR YOUR ACCOUNT AND RESPONSIBILITY FOR ANY DIFFICULTIES OCCURRING ON CUSTOMER'S PROPERTY, DUE TO YOUR LUBRICATOR, ARE TO REST BETWEEN YOUR COMPANY AND THE RAILROAD."

AND TO BE SO NOTED ON CONTRACT BILL OF MATERIAL.

WESTINGHOUSE AIR BRAKE AIR COMPRESSOR AND MECHANICAL LUBRICATOR

WHEN THE WESTINGHOUSE AIR BRAKE COMPANY'S LUBRICATOR IS REQUIRED IT SHALL BE FURNISHED APPLIED ON THE AIR COMPRESSOR BY THE WESTINGHOUSE AIR BRAKE COMPANY.

THE BALDWIN LOCOMOTIVE WORKS SHALL SPECIFY ON THE PURCHASE ORDER THE DRAWING NUMBER OF THE WESTINGHOUSE AIR BRAKE COMPANY'S INSTALLATION ARRANGEMENT DESIRED AND THE PIECE NUMBER OF THE LUBRICATOR BRACKET.

THE BALDWIN LOCOMOTIVE WORKS WILL SUPPLY THE COPPER TUBING REQUIRED FOR THE FOLLOWING CONNECTIONS:- HEATER FROM LUBRICATOR TO GOVERNOR, OIL DELIVERY TO AIR END AND TO STEAM END OF GOVERNOR.

(CONTINUED)